

**REQUIRED DIGITAL DRAWING SUBMITTALS:**

Digital file(s), acceptable to Public Works, shall be provided for any/all of the following:

- 1) Final Plats or Plat Amendments, before the Plat(s) or Plat Amendment(s) will be recorded.
- 2) Civil Construction Plans (CD's) for Streets and/or Storm Sewer Systems (including all drainage system, swales, permanent water quality features and storm water detention facilities), before construction may begin.
- 3) Drawing of Record (Record Drawings/As-Builts): Following completion of construction of the facilities noted under Item #2 above, before final Project acceptance by the City.

**Required Format:** The required Digital AutoCad file(s) noted above shall be consistent with the NAD83 Colorado State Plane, Central Zone, US FEET, and shall have at least one surveyed point located relative to one of the City of Lone Tree control points. An AutoCAD (.dwg) file containing all Lone Tree control points is available on the City website at

<http://cityoflonetree.hosted.civiclive.com/cms/One.aspx?portalId=745982&pageId=1944722> .

(Updated 1-21-16)